

Summary Treatment Report Version: 4.3.5

Project: Church of the Ascension

Analysis Type: Specified Removal

Date:4/11/2026

Efficiency

BMP Types:

Routing Summary

Catchment 1 - (Basin) Multiple BMP Catchment 1 Routed to Outlet
Based on % removal values to the
nearest percent

Total nitrogen target removal met? **No**

Total phosphorus target removal met? **No**

Summary Report

Nitrogen

Surface Water Discharge

Total N pre load	23.11 kg/yr	
Total N post load	24.74 kg/yr	
Target N load reduction	95 %	
Target N discharge load	1.24 kg/yr	
Percent N load reduction	83 %	
Provided N discharge load	4.24 kg/yr	9.35 lb/yr
Provided N load removed	20.5 kg/yr	45.21 lb/yr

Phosphorus

Surface Water Discharge

Total P pre load	3.844 kg/yr	
Total P post load	4.116 kg/yr	
Target P load reduction	95 %	
Target P discharge load	.206 kg/yr	
Percent P load reduction	93 %	
Provided P discharge load	.296 kg/yr	.65 lb/yr
Provided P load removed	3.821 kg/yr	8.424 lb/yr